

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER THREE RIVERS 32-35-720				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT WILDCAT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR AXIA ENERGY LLC						7. OPERATOR PHONE 720 746-5200				
8. ADDRESS OF OPERATOR 1430 Larimer Ste 400, Denver, CO, 80202						9. OPERATOR E-MAIL rsatre@axiaenergy.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) FEE			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Kay Anderson						14. SURFACE OWNER PHONE (if box 12 = 'fee') 801-224-2907				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 683 W. 925 S., Orem, UT 84058						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		535 FSL 2180 FWL		SESW	32	7.0 S	20.0 E	S		
Top of Uppermost Producing Zone		460 FSL 2180 FWL		SESW	32	7.0 S	20.0 E	S		
At Total Depth		460 FSL 2180 FWL		SESW	32	7.0 S	20.0 E	S		
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 460			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1200			26. PROPOSED DEPTH MD: 9006 TVD: 9004				
27. ELEVATION - GROUND LEVEL 4790			28. BOND NUMBER LPM9046682			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 49-2262 - RNI at Green River				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	11	8.625	0 - 1100	32.0	J-55 LT&C	8.7	Premium Lite High Strength	110	2.97	11.5
							Class G	115	1.16	15.8
PROD	7.875	5.5	0 - 9006	17.0	N-80 LT&C	9.2	Premium Lite High Strength	570	2.31	12.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent (Buys & Associates, Inc)				PHONE 435 719-2018		
SIGNATURE				DATE 05/23/2012				EMAIL starpoint@etv.net		
API NUMBER ASSIGNED 43047527370000				APPROVAL Permit Manager						

DRILLING PLAN

Axia Energy, LLC
Three Rivers Project
Three Rivers #32-35-720
SESW Sec 32 T7S R20E
Uintah County, Utah

1. ESTIMATED FORMATION TOPS

FORMATION	TOP (TVD)	COMMENTS
Uinta	Surface	Gas & Degraded Oil; Possible Brackish H ₂ O
Green River	3,088'	Oil & Associated Gas
Lower Green River*	5,095'	Oil & Associated Gas
Wasatch*	7,004'	Oil & Associated Gas
TD	9,006' (MD)	9,004' (TVD)

NOTE: Datum, Ground Level (GL) Elevation: 4,790'; Asterisks (*) denotes target pay intervals

A) The State of Utah, Division of Oil, Gas and Mining will be notified within 24 hours of spudding the well.

2. CASING PROGRAM

CASING	HOLE SIZE	DEPTH SET (MD)	CSG SIZE	WGHT	GRD	THRD	CAPACITY (bbl/ft)
CONDUCTOR		50-75	13 3/8				
SURFACE	11	1100 ±	8 5/8	32.0	J-55	LTC	0.0609
PRODUCTION	7 7/8	9,006'	5 1/2	17.0	N-80	LTC	0.0232

NOTE: All casing depth intervals are to surface unless otherwise noted.

Casing Specs

SIZE (in)	ID (in)	DRIFT DIA (in)	COLLAPSE RESISTANCE (psi)	INTERNAL YIELD (psi)	TENSILE YIELD (lbs)	JOINT STRENGTH (lbs)
8 5/8	7.921	7.796	2,530	3,930	503,000	417,000
5 1/2	4.892	4.767	6,280	7,740	397,000	348,000

*The State of Utah will be notified 24 hours prior to running casing, cementing, and BOPE testing

FLOAT EQUIPMENT

SURFACE (8 5/8): Float Shoe, 1 JNT Casing, Float Collar
Centralizers: 1st 4 Joints: every joint
Remainder: every third joint

PRODUCTION (5 1/2): Float Shoe, 1 JNT Casing, Float Collar
Centralizers: 1st 4 Joints: every joint
Remainder: every third joint 500' into surface casing

NOTE: 5 1/2" 17# N-80 or equivalent marker collar or casing joints will be placed at the top of the Green River and approximately 400' above the Wasatch.

3. CEMENT PROGRAM

CONDUCTOR (13 3/8): Ready Mix – Cement to surface

SURFACE (8 5/8): Cement Top: Surface
Lead: 110 sks, Premium Lightweight Cmt w/ additives, 11.50 ppg, 2.97 cf/sk, 50% excess
Tail: 115 sks Class G Cement w/ additives, 15.80 ppg, 1.16 cf/sk, 50% excess

NOTE: The above volumes are based on a gauge-hole + 50% excess.

PRODUCTION (5 1/2): Cement Top – 2,700'
570 sacks – Light Premium Cement w/ additives – 12.0 ppg, 2.31 ft³/sk – 20% excess

NOTE: The above volumes are based on gauge hole + 20% excess. Adjustments will be made and volumes will be caliper + 10%.

NOTE: The above volumes are based on a gauged-hole. Adjustments will be made based on caliper.

- A) For Surface casing, if cement falls or does not circulate to surface, cement will be topped off.
- B) Cement will not be placed down annulus with a 1" pipe unless BLM is contacted.
- C) The State of Utah will be notified 24 hours prior to running casing and cementing.

4. PRESSURE CONTROL EQUIPMENT

- A) The State of Utah, Division of Oil, Gas and Mining will be notified 24 hours prior to all BOPE pressure tests.
- B) The BOPE shall be closed whenever the well is unattended.
 - a) All BOPE connections subjected to well pressure will be flanged, welded, or clamped.
 - b) Choke Manifold:

- i) Tee blocks or targeted 'T's will be used and anchored to prevent slip and reduce vibration.
- ii) Two adjustable chokes will be used in the choke manifold.
- iii) All valves (except chokes) in kill line choke manifold and choke line will not restrict the flow.
- iv) Pressure gauges in the well control system will be designed for drilling fluid.

C) BOPE Testing:

- a) BOPE shall be pressure tested when initially installed, whenever any seal subject to pressure testing is broken, or after repairs.
- b) All BOP tests will be performed with a test plug in place.
- c) BOP will be tested to full stack working pressure and annular preventer to 50% stack working pressure.

INTERVAL	BOP EQUIPMENT
0 – 1100 ±	11" Diverter with Rotating Head
1100 ± – TD	3,000# Ram Double BOP & Annular with Diverter & Rotating Head

NOTE: Drilling spool to accommodate choke and kill lines.

5. **MUD PROGRAM**

- A) Mud test will be performed at least every 24 hours and after mudding up to determine density, viscosity, gel strength, filtration, and pH.
- B) Gas-detecting equipment will be installed and operated in the mud-return system from top of Green River Formation to TD.
 - a) Flare line discharge will be located no less than 100 feet from the wellhead using straight or targeted 'T's and anchors.

INTERVAL	MUD WGHT	VISC	FLUID LOSS	COMMENTS
SURF – 1100 ±	8.4 – 8.7 ppg	32	NC	Spud Mud
1100 ± – TD	8.6 – 9.2 ppg	40	NC	DAP/Gel

NOTE: Mud weight increases will be directed by hole conditions.

6. **ABNORMAL CONDITIONS**

- A) No abnormal pressures or temperatures are anticipated.
 - a) Estimated bottom hole pressure at TD will be approximately 3,899 psi (normal pressure gradient: 0.433 psi/ft).
 - b) Estimated maximum surface pressure will be approximately 1,981 psi (estimated bottom hole minus pressure of partially evacuated hole (gradient: 0.220 psi/ft)).
- B) No hydrogen sulfide is anticipated.

INTERVAL	CONDITION
SURF – 1100 ±	Lost Circulation Possible
1100 ± – TD	Lost Circulation Possible

7. **AUXILIARY EQUIPMENT**

- A) Choke Manifold

- B) Upper and lower kelly cock with handle available
- C) Stabbing valve
- D) Safety valve and subs to fit all string connections in use

8. **SURVEY & LOGGING PROGRAMS**

- A) Cores: None anticipated.
- B) Testing: None anticipated.
- C) Directional Drilling: Directional tools will be used to locate the bottom hole per the attached directional plan +/-.
- D) Open Hole Logs: TD to surface casing: resistivity, neutron density, gamma ray and caliper.
- E) Mud Logs: Computerized 2-person logging unit will catch and describe 10 foot samples from top of Green River Formation to TD; record and monitor gas shows and record drill times (normal mud logging duties).

9. **HAZARDOUS MATERIALS**

In accordance with Superfund Amendments and Reauthorization Act of 1986 (SARA) Title III, no chemicals subject to reporting in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well.

T7S, R20E, S.L.B.&M.

AXIA ENERGY



Well location, THREE RIVERS #32-35-720, located as shown in the SE 1/4 SW 1/4 of Section 32, T7S, R20E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION 9, T7S, R20E, S.L.B.&M. TAKEN FROM THE PELICAN LAKE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4942 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
KAX
REGISTRATION NO. 161319
STATE OF UTAH
05-03-12


LINE TABLE	
LINE	DIRECTION LENGTH
L1	S01°40'26\"E 75.05'

NAD 83 (TARGET BOTTOM HOLE)		NAD 83 (SURFACE LOCATION)	
LATITUDE = 40°09'35.96\"	(40.159989)	LATITUDE = 40°09'36.70\"	(40.160194)
LONGITUDE = 109°41'39.79\"	(109.694386)	LONGITUDE = 109°41'39.82\"	(109.694394)
NAD 27 (TARGET BOTTOM HOLE)		NAD 27 (SURFACE LOCATION)	
LATITUDE = 40°09'36.09\"	(40.160025)	LATITUDE = 40°09'36.83\"	(40.160231)
LONGITUDE = 109°41'37.29\"	(109.693692)	LONGITUDE = 109°41'37.32\"	(109.693700)

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1\" = 1000'	DATE SURVEYED: 02-03-12	DATE DRAWN: 04-20-12
----------------------	----------------------------	-------------------------

PARTY C.R. S.R. R.L.L.	REFERENCES G.L.O. PLAT
WEATHER COOL	FILE AXIA ENERGY



LEGEND:

● PROPOSED LOCATION



AXIA ENERGY

THREE RIVERS #32-35-720
SECTION 32, T7S, R20E, S.L.B.&M.
535' FSL 2180' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

ACCESS ROAD
MAP

04 27 12
 MONTH DAY YEAR


SCALE: 1:100,000

DRAWN BY: C.I.

REVISED: 06-25-12





 EXISTING ROAD
 PROPOSED ACCESS ROAD
 EXISTING POWER LINE



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

**AXIA ENERGY**

**THREE RIVERS #32-35-720
SECTION 32, T7S, R20E, S.L.B.&M.
535' FSL 2180' FWL**

ACCESS ROAD MAP

04 27 12
MONTH DAY YEAR


SCALE: 1" = 2000'

DRAWN BY: C.I.

REVISÉD: 06-25-12

B

TOPO



LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

N



AXIA ENERGY

**THREE RIVERS #32-35-720
SECTION 32, T7S, R20E, S.L.B.&M.
535' FSL 2180' FWL**




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**

04 27 12
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.I. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 169' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE
(SERVICING OTHER WELLS)

N

AXIA ENERGY

**THREE RIVERS #32-35-720
SECTION 32, T7S, R20E, S.L.B.&M.
535' FSL 2180' FWL**



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**


04 27 12
MONTH DAY YEAR

SCALE: 1" = 2000'

DRAWN BY: C.I.

REVISED: 06-25-12

**D
TOPO**



APPROXIMATE TOTAL POWER LINE DISTANCE = 198' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- PROPOSED POWER LINE
- PROPOSED POWER LINE (SERVICING OTHER WELLS)

N

AXIA ENERGY

THREE RIVERS #32-35-720
SECTION 32, T7S, R20E, S.L.B.&M.
535' FSL 2180' FWL



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

04 27 12
MONTH DAY YEAR

SCALE: 1" = 2000'

DRAWN BY: C.I.

REVISED: 06-25-12

E
TOPO

Planning Report

Database:	USA EDM 5000 Multi Users DB	Local Co-ordinate Reference:	Well Three Rivers #32-35-720
Company:	Axia Energy	TVD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Project:	Uintah County, UT	MD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Site:	SEC 32-T7S-R20E	North Reference:	True
Well:	Three Rivers #32-35-720	Survey Calculation Method:	Minimum Curvature
Wellbore:	DD		
Design:	Plan #1		

Project	Uintah County, UT		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Northern Zone		

Site		SEC 32-T7S-R20E			
Site Position:		Northing:	3,224,156.48 ft	Latitude:	40.163383
From:	Lat/Long	Easting:	2,144,775.24 ft	Longitude:	-109.695589
Position Uncertainty:	0.0 ft	Slot Radius:	13.200 in	Grid Convergence:	1.19 °

Well	Three Rivers #32-35-720					
Well Position	+N/-S	0.0 ft	Northing:	3,223,001.76 ft	Latitude:	40.160194
	+E/-W	0.0 ft	Easting:	2,145,133.35 ft	Longitude:	-109.694394
Position Uncertainty		0.0 ft	Wellhead Elevation:	ft	Ground Level:	4,791.0 ft

Wellbore	DD				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	5/15/2012	11.06	65.94	52,299

Design	Plan #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.0	0.0	0.0	178.28

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,159.5	3.19	178.28	1,159.4	-4.4	0.1	2.00	2.00	0.00	178.28	
2,342.5	3.19	178.28	2,340.6	-70.2	2.1	0.00	0.00	0.00	0.00	
2,502.0	0.00	0.00	2,500.0	-74.7	2.2	2.00	-2.00	0.00	180.00	
9,006.0	0.00	0.00	9,004.0	-74.7	2.2	0.00	0.00	0.00	0.00	Three Rivers #32-35-

Planning Report

Database: USA EDM 5000 Multi Users DB
Company: Axia Energy
Project: Uintah County, UT
Site: SEC 32-T7S-R20E
Well: Three Rivers #32-35-720
Wellbore: DD
Design: Plan #1

Local Co-ordinate Reference: Well Three Rivers #32-35-720
TVD Reference: KB=16' @ 4807.0ft (Original Well Elev)
MD Reference: KB=16' @ 4807.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Comments / Formations
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	KOP @ 1000'
1,100.0	2.00	178.28	1,100.0	-1.7	0.1	1.7	2.00	2.00	
1,159.5	3.19	178.28	1,159.4	-4.4	0.1	4.4	2.00	2.00	EOB; Inc=3.19°
1,200.0	3.19	178.28	1,199.9	-6.7	0.2	6.7	0.00	0.00	
1,300.0	3.19	178.28	1,299.7	-12.3	0.4	12.3	0.00	0.00	
1,400.0	3.19	178.28	1,399.5	-17.8	0.5	17.8	0.00	0.00	
1,500.0	3.19	178.28	1,499.4	-23.4	0.7	23.4	0.00	0.00	
1,600.0	3.19	178.28	1,599.2	-28.9	0.9	29.0	0.00	0.00	
1,700.0	3.19	178.28	1,699.1	-34.5	1.0	34.5	0.00	0.00	
1,800.0	3.19	178.28	1,798.9	-40.1	1.2	40.1	0.00	0.00	
1,900.0	3.19	178.28	1,898.8	-45.6	1.4	45.7	0.00	0.00	
2,000.0	3.19	178.28	1,998.6	-51.2	1.5	51.2	0.00	0.00	
2,100.0	3.19	178.28	2,098.5	-56.8	1.7	56.8	0.00	0.00	
2,200.0	3.19	178.28	2,198.3	-62.3	1.9	62.3	0.00	0.00	
2,300.0	3.19	178.28	2,298.1	-67.9	2.0	67.9	0.00	0.00	
2,342.5	3.19	178.28	2,340.6	-70.2	2.1	70.3	0.00	0.00	Start Drop -2.00
2,400.0	2.04	178.28	2,398.0	-72.9	2.2	72.9	2.00	-2.00	
2,500.0	0.04	178.28	2,498.0	-74.7	2.2	74.7	2.00	-2.00	
2,502.0	0.00	0.00	2,500.0	-74.7	2.2	74.7	2.00	-2.00	EOD; Inc=0°
2,600.0	0.00	0.00	2,598.0	-74.7	2.2	74.7	0.00	0.00	
2,700.0	0.00	0.00	2,698.0	-74.7	2.2	74.7	0.00	0.00	
2,800.0	0.00	0.00	2,798.0	-74.7	2.2	74.7	0.00	0.00	
2,900.0	0.00	0.00	2,898.0	-74.7	2.2	74.7	0.00	0.00	
3,000.0	0.00	0.00	2,998.0	-74.7	2.2	74.7	0.00	0.00	
3,090.0	0.00	0.00	3,088.0	-74.7	2.2	74.7	0.00	0.00	Top Green River
3,100.0	0.00	0.00	3,098.0	-74.7	2.2	74.7	0.00	0.00	
3,200.0	0.00	0.00	3,198.0	-74.7	2.2	74.7	0.00	0.00	
3,300.0	0.00	0.00	3,298.0	-74.7	2.2	74.7	0.00	0.00	
3,400.0	0.00	0.00	3,398.0	-74.7	2.2	74.7	0.00	0.00	
3,401.0	0.00	0.00	3,399.0	-74.7	2.2	74.7	0.00	0.00	Top Birds Nest
3,500.0	0.00	0.00	3,498.0	-74.7	2.2	74.7	0.00	0.00	
3,600.0	0.00	0.00	3,598.0	-74.7	2.2	74.7	0.00	0.00	
3,700.0	0.00	0.00	3,698.0	-74.7	2.2	74.7	0.00	0.00	
3,800.0	0.00	0.00	3,798.0	-74.7	2.2	74.7	0.00	0.00	
3,870.0	0.00	0.00	3,868.0	-74.7	2.2	74.7	0.00	0.00	Base Birds Nest
3,900.0	0.00	0.00	3,898.0	-74.7	2.2	74.7	0.00	0.00	
4,000.0	0.00	0.00	3,998.0	-74.7	2.2	74.7	0.00	0.00	
4,080.0	0.00	0.00	4,078.0	-74.7	2.2	74.7	0.00	0.00	Temperature 120
4,100.0	0.00	0.00	4,098.0	-74.7	2.2	74.7	0.00	0.00	
4,200.0	0.00	0.00	4,198.0	-74.7	2.2	74.7	0.00	0.00	
4,300.0	0.00	0.00	4,298.0	-74.7	2.2	74.7	0.00	0.00	
4,400.0	0.00	0.00	4,398.0	-74.7	2.2	74.7	0.00	0.00	

Planning Report

Database: USA EDM 5000 Multi Users DB
Company: Axia Energy
Project: Uintah County, UT
Site: SEC 32-T7S-R20E
Well: Three Rivers #32-35-720
Wellbore: DD
Design: Plan #1

Local Co-ordinate Reference: Well Three Rivers #32-35-720
TVD Reference: KB=16' @ 4807.0ft (Original Well Elev)
MD Reference: KB=16' @ 4807.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Comments / Formations
4,500.0	0.00	0.00	4,498.0	-74.7	2.2	74.7	0.00	0.00	
4,600.0	0.00	0.00	4,598.0	-74.7	2.2	74.7	0.00	0.00	
4,700.0	0.00	0.00	4,698.0	-74.7	2.2	74.7	0.00	0.00	
4,800.0	0.00	0.00	4,798.0	-74.7	2.2	74.7	0.00	0.00	
4,900.0	0.00	0.00	4,898.0	-74.7	2.2	74.7	0.00	0.00	
5,000.0	0.00	0.00	4,998.0	-74.7	2.2	74.7	0.00	0.00	
5,097.0	0.00	0.00	5,095.0	-74.7	2.2	74.7	0.00	0.00	Garden Gulch (MGR Marker)
5,100.0	0.00	0.00	5,098.0	-74.7	2.2	74.7	0.00	0.00	
5,200.0	0.00	0.00	5,198.0	-74.7	2.2	74.7	0.00	0.00	
5,300.0	0.00	0.00	5,298.0	-74.7	2.2	74.7	0.00	0.00	
5,400.0	0.00	0.00	5,398.0	-74.7	2.2	74.7	0.00	0.00	
5,500.0	0.00	0.00	5,498.0	-74.7	2.2	74.7	0.00	0.00	
5,600.0	0.00	0.00	5,598.0	-74.7	2.2	74.7	0.00	0.00	
5,700.0	0.00	0.00	5,698.0	-74.7	2.2	74.7	0.00	0.00	
5,800.0	0.00	0.00	5,798.0	-74.7	2.2	74.7	0.00	0.00	
5,900.0	0.00	0.00	5,898.0	-74.7	2.2	74.7	0.00	0.00	
6,000.0	0.00	0.00	5,998.0	-74.7	2.2	74.7	0.00	0.00	
6,100.0	0.00	0.00	6,098.0	-74.7	2.2	74.7	0.00	0.00	
6,200.0	0.00	0.00	6,198.0	-74.7	2.2	74.7	0.00	0.00	
6,300.0	0.00	0.00	6,298.0	-74.7	2.2	74.7	0.00	0.00	
6,400.0	0.00	0.00	6,398.0	-74.7	2.2	74.7	0.00	0.00	
6,500.0	0.00	0.00	6,498.0	-74.7	2.2	74.7	0.00	0.00	
6,600.0	0.00	0.00	6,598.0	-74.7	2.2	74.7	0.00	0.00	
6,700.0	0.00	0.00	6,698.0	-74.7	2.2	74.7	0.00	0.00	
6,800.0	0.00	0.00	6,798.0	-74.7	2.2	74.7	0.00	0.00	
6,856.0	0.00	0.00	6,854.0	-74.7	2.2	74.7	0.00	0.00	Top Uteland Butte (LGR Marker)
6,900.0	0.00	0.00	6,898.0	-74.7	2.2	74.7	0.00	0.00	
7,000.0	0.00	0.00	6,998.0	-74.7	2.2	74.7	0.00	0.00	
7,006.0	0.00	0.00	7,004.0	-74.7	2.2	74.7	0.00	0.00	Top Wasatch (Base Uteland)
7,100.0	0.00	0.00	7,098.0	-74.7	2.2	74.7	0.00	0.00	
7,200.0	0.00	0.00	7,198.0	-74.7	2.2	74.7	0.00	0.00	
7,300.0	0.00	0.00	7,298.0	-74.7	2.2	74.7	0.00	0.00	
7,400.0	0.00	0.00	7,398.0	-74.7	2.2	74.7	0.00	0.00	
7,500.0	0.00	0.00	7,498.0	-74.7	2.2	74.7	0.00	0.00	
7,600.0	0.00	0.00	7,598.0	-74.7	2.2	74.7	0.00	0.00	
7,700.0	0.00	0.00	7,698.0	-74.7	2.2	74.7	0.00	0.00	
7,800.0	0.00	0.00	7,798.0	-74.7	2.2	74.7	0.00	0.00	
7,900.0	0.00	0.00	7,898.0	-74.7	2.2	74.7	0.00	0.00	
8,000.0	0.00	0.00	7,998.0	-74.7	2.2	74.7	0.00	0.00	
8,100.0	0.00	0.00	8,098.0	-74.7	2.2	74.7	0.00	0.00	
8,200.0	0.00	0.00	8,198.0	-74.7	2.2	74.7	0.00	0.00	
8,300.0	0.00	0.00	8,298.0	-74.7	2.2	74.7	0.00	0.00	
8,400.0	0.00	0.00	8,398.0	-74.7	2.2	74.7	0.00	0.00	
8,500.0	0.00	0.00	8,498.0	-74.7	2.2	74.7	0.00	0.00	
8,600.0	0.00	0.00	8,598.0	-74.7	2.2	74.7	0.00	0.00	
8,700.0	0.00	0.00	8,698.0	-74.7	2.2	74.7	0.00	0.00	
8,800.0	0.00	0.00	8,798.0	-74.7	2.2	74.7	0.00	0.00	
8,900.0	0.00	0.00	8,898.0	-74.7	2.2	74.7	0.00	0.00	
9,000.0	0.00	0.00	8,998.0	-74.7	2.2	74.7	0.00	0.00	
9,006.0	0.00	0.00	9,004.0	-74.7	2.2	74.7	0.00	0.00	TD at 9006.0 - Three Rivers #32-35-720 PBHL

Planning Report

Database:	USA EDM 5000 Multi Users DB	Local Co-ordinate Reference:	Well Three Rivers #32-35-720
Company:	Axia Energy	TVD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Project:	Uintah County, UT	MD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Site:	SEC 32-T7S-R20E	North Reference:	True
Well:	Three Rivers #32-35-720	Survey Calculation Method:	Minimum Curvature
Wellbore:	DD		
Design:	Plan #1		

Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)		
Three Rivers #32-35-720 - plan hits target center - Circle (radius 50.0)	0.00	0.00	9,004.0	-74.7	2.2	3,222,927.14	2,145,137.14	40.159989	-109.694386

Formations						
Measured Depth	Vertical Depth	Name	Lithology	Dip	Dip Direction	
(ft)	(ft)			(°)	(°)	
3,090.0	3,088.0	Top Green River				
3,401.0	3,399.0	Top Birds Nest				
3,870.0	3,868.0	Base Birds Nest				
4,080.0	4,078.0	Temperature 120				
5,097.0	5,095.0	Garden Gulch (MGR Marker)				
6,856.0	6,854.0	Top Uteland Butte (LGR Marker)				
7,006.0	7,004.0	Top Wasatch (Base Uteland)				

Plan Annotations				
Measured Depth	Vertical Depth	Local Coordinates		Comment
(ft)	(ft)	+N/-S (ft)	+E/-W (ft)	
1,000.0	1,000.0	0.0	0.0	KOP @ 1000'
1,159.5	1,159.4	-4.4	0.1	EOB; Inc=3.19°
2,342.5	2,340.6	-70.2	2.1	Start Drop -2.00
2,502.0	2,500.0	-74.7	2.2	EOD; Inc=0°
9,006.0	9,004.0	-74.7	2.2	TD at 9006.0

Axia Energy

Uintah County, UT

SEC 32-T7S-R20E

Three Rivers #32-35-720

DD

Plan #1

Anticollision Report

15 May, 2012

Anticollision Report

Company:	Axia Energy	Local Co-ordinate Reference:	Well Three Rivers #32-35-720
Project:	Uintah County, UT	TVD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Reference Site:	SEC 32-T7S-R20E	MD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Site Error:	0.0ft	North Reference:	True
Reference Well:	Three Rivers #32-35-720	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0ft	Output errors are at	2.00 sigma
Reference Wellbore	DD	Database:	USA EDM 5000 Multi Users DB
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum

Reference	Plan #1
Filter type:	GLOBAL FILTER APPLIED: All wellpaths within 200'+ 100/1000 of reference
Interpolation Method:	MD Interval 100.0ft
Depth Range:	Unlimited
Results Limited by:	Maximum center-center distance of 1,100.6ft
Warning Levels Evaluated at:	2.00 Sigma
Error Model:	ISCWSA
Scan Method:	Closest Approach 3D
Error Surface:	Elliptical Conic

Survey Tool Program	Date	5/15/2012
From (ft)	To (ft)	Survey (Wellbore)
0.0	9,005.4	Plan #1 (DD)
		Tool Name
		MWD
		Description
		Geolink MWD

Summary						
Site Name	Reference Measured Depth (ft)	Offset Measured Depth (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
SEC 32-T7S-R20E						
Three Rivers #32-34-720 - DD - Plan #1	9,006.0	9,038.3	867.1	835.4	27.385	CC, ES, SF

Anticollision Report

Company:	Axia Energy	Local Co-ordinate Reference:	Well Three Rivers #32-35-720
Project:	Uintah County, UT	TVD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Reference Site:	SEC 32-T7S-R20E	MD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Site Error:	0.0ft	North Reference:	True
Reference Well:	Three Rivers #32-35-720	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0ft	Output errors are at	2.00 sigma
Reference Wellbore	DD	Database:	USA EDM 5000 Multi Users DB
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum

Offset Design SEC 32-T7S-R20E - Three Rivers #32-34-720 - DD - Plan #1													Offset Site Error:	0.0 ft
Survey Program: O-MWD													Offset Well Error:	0.0 ft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Total Uncertainty Axis	Separation Factor		
2,100.0	2,098.5	2,285.1	2,272.0	3.8	5.1	168.57	997.3	-246.1	1,096.3	1,088.6	7.71	142.236		
2,200.0	2,198.3	2,384.4	2,370.0	4.0	5.4	168.87	983.2	-238.0	1,086.1	1,078.0	8.07	134.508		
2,300.0	2,298.1	2,483.7	2,468.0	4.2	5.7	169.19	969.2	-229.9	1,075.9	1,067.4	8.44	127.434		
2,400.0	2,398.0	2,582.9	2,565.9	4.4	6.0	169.48	955.2	-221.8	1,065.2	1,056.3	8.81	120.891		
2,500.0	2,498.0	2,681.8	2,663.5	4.5	6.3	169.71	941.2	-213.7	1,051.4	1,042.2	9.17	114.641		
2,600.0	2,598.0	2,780.5	2,760.8	4.7	6.6	-11.72	927.2	-205.7	1,035.8	1,026.3	9.54	108.583		
2,700.0	2,698.0	2,879.1	2,858.1	4.9	7.0	-11.44	913.3	-197.7	1,020.3	1,010.4	9.91	102.959		
2,800.0	2,798.0	2,977.8	2,955.5	5.0	7.3	-11.14	899.3	-189.6	1,004.8	994.5	10.28	97.727		
2,900.0	2,898.0	3,076.5	3,052.8	5.2	7.6	-10.84	885.4	-181.6	989.4	978.7	10.66	92.848		
3,000.0	2,998.0	3,175.1	3,150.1	5.4	7.9	-10.52	871.4	-173.5	973.9	962.9	11.03	88.287		
3,100.0	3,098.0	3,273.8	3,247.5	5.5	8.2	-10.20	857.5	-165.5	958.5	947.1	11.41	84.016		
3,200.0	3,198.0	3,372.4	3,344.8	5.7	8.6	-9.86	843.5	-157.4	943.2	931.4	11.79	80.007		
3,300.0	3,298.0	3,471.1	3,442.1	5.9	8.9	-9.52	829.6	-149.4	927.8	915.7	12.17	76.237		
3,400.0	3,398.0	3,568.1	3,537.8	6.0	9.2	-9.17	815.9	-141.5	912.5	900.0	12.55	72.709		
3,500.0	3,498.0	3,644.4	3,613.3	6.2	9.4	-8.91	806.1	-135.8	898.7	885.8	12.88	69.763		
3,600.0	3,598.0	3,721.3	3,689.6	6.4	9.6	-8.69	798.0	-131.1	887.3	874.1	13.21	67.177		
3,700.0	3,698.0	3,800.0	3,768.0	6.6	9.8	-8.51	791.5	-127.4	878.5	864.9	13.53	64.913		
3,800.0	3,798.0	3,876.3	3,844.1	6.7	9.9	-8.39	787.0	-124.8	872.1	858.3	13.84	62.995		
3,900.0	3,898.0	3,954.3	3,922.0	6.9	10.0	-8.31	784.3	-123.2	868.4	854.2	14.15	61.354		
4,000.0	3,998.0	4,032.3	4,000.0	7.1	10.1	-8.29	783.4	-122.7	867.1	852.6	14.46	59.978		
4,100.0	4,098.0	4,132.3	4,100.0	7.2	10.3	-8.29	783.4	-122.7	867.1	852.3	14.79	58.608		
4,200.0	4,198.0	4,232.3	4,200.0	7.4	10.4	-8.29	783.4	-122.7	867.1	852.0	15.13	57.298		
4,300.0	4,298.0	4,332.3	4,300.0	7.6	10.5	-8.29	783.4	-122.7	867.1	851.6	15.47	56.043		
4,400.0	4,398.0	4,432.3	4,400.0	7.8	10.6	-8.29	783.4	-122.7	867.1	851.3	15.81	54.841		
4,500.0	4,498.0	4,532.3	4,500.0	7.9	10.8	-8.29	783.4	-122.7	867.1	850.9	16.15	53.688		
4,600.0	4,598.0	4,632.3	4,600.0	8.1	10.9	-8.29	783.4	-122.7	867.1	850.6	16.49	52.581		
4,700.0	4,698.0	4,732.3	4,700.0	8.3	11.0	-8.29	783.4	-122.7	867.1	850.3	16.83	51.518		
4,800.0	4,798.0	4,832.3	4,800.0	8.5	11.2	-8.29	783.4	-122.7	867.1	849.9	17.17	50.496		
4,900.0	4,898.0	4,932.3	4,900.0	8.6	11.3	-8.29	783.4	-122.7	867.1	849.6	17.51	49.512		
5,000.0	4,998.0	5,032.3	5,000.0	8.8	11.4	-8.29	783.4	-122.7	867.1	849.2	17.85	48.566		
5,100.0	5,098.0	5,132.3	5,100.0	9.0	11.6	-8.29	783.4	-122.7	867.1	848.9	18.20	47.654		
5,200.0	5,198.0	5,232.3	5,200.0	9.1	11.7	-8.29	783.4	-122.7	867.1	848.5	18.54	46.775		
5,300.0	5,298.0	5,332.3	5,300.0	9.3	11.8	-8.29	783.4	-122.7	867.1	848.2	18.88	45.928		
5,400.0	5,398.0	5,432.3	5,400.0	9.5	12.0	-8.29	783.4	-122.7	867.1	847.9	19.22	45.110		
5,500.0	5,498.0	5,532.3	5,500.0	9.7	12.1	-8.29	783.4	-122.7	867.1	847.5	19.56	44.320		
5,600.0	5,598.0	5,632.3	5,600.0	9.8	12.2	-8.29	783.4	-122.7	867.1	847.2	19.91	43.557		
5,700.0	5,698.0	5,732.3	5,700.0	10.0	12.4	-8.29	783.4	-122.7	867.1	846.8	20.25	42.819		
5,800.0	5,798.0	5,832.3	5,800.0	10.2	12.5	-8.29	783.4	-122.7	867.1	846.5	20.59	42.105		
5,900.0	5,898.0	5,932.3	5,900.0	10.4	12.7	-8.29	783.4	-122.7	867.1	846.2	20.94	41.415		
6,000.0	5,998.0	6,032.3	6,000.0	10.5	12.8	-8.29	783.4	-122.7	867.1	845.8	21.28	40.746		
6,100.0	6,098.0	6,132.3	6,100.0	10.7	13.0	-8.29	783.4	-122.7	867.1	845.5	21.62	40.098		
6,200.0	6,198.0	6,232.3	6,200.0	10.9	13.1	-8.29	783.4	-122.7	867.1	845.1	21.97	39.471		
6,300.0	6,298.0	6,332.3	6,300.0	11.0	13.2	-8.29	783.4	-122.7	867.1	844.8	22.31	38.862		
6,400.0	6,398.0	6,432.3	6,400.0	11.2	13.4	-8.29	783.4	-122.7	867.1	844.4	22.66	38.272		
6,500.0	6,498.0	6,532.3	6,500.0	11.4	13.5	-8.29	783.4	-122.7	867.1	844.1	23.00	37.699		
6,600.0	6,598.0	6,632.3	6,600.0	11.6	13.7	-8.29	783.4	-122.7	867.1	843.7	23.34	37.142		
6,700.0	6,698.0	6,732.3	6,700.0	11.7	13.8	-8.29	783.4	-122.7	867.1	843.4	23.69	36.602		
6,800.0	6,798.0	6,832.3	6,800.0	11.9	14.0	-8.29	783.4	-122.7	867.1	843.1	24.03	36.077		
6,900.0	6,898.0	6,932.3	6,900.0	12.1	14.1	-8.29	783.4	-122.7	867.1	842.7	24.38	35.567		
7,000.0	6,998.0	7,032.3	7,000.0	12.3	14.3	-8.29	783.4	-122.7	867.1	842.4	24.72	35.070		
7,100.0	7,098.0	7,132.3	7,100.0	12.4	14.4	-8.29	783.4	-122.7	867.1	842.0	25.07	34.588		
7,200.0	7,198.0	7,232.3	7,200.0	12.6	14.6	-8.29	783.4	-122.7	867.1	841.7	25.41	34.118		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	Axia Energy	Local Co-ordinate Reference:	Well Three Rivers #32-35-720
Project:	Uintah County, UT	TVD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Reference Site:	SEC 32-T7S-R20E	MD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Site Error:	0.0ft	North Reference:	True
Reference Well:	Three Rivers #32-35-720	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0ft	Output errors are at	2.00 sigma
Reference Wellbore	DD	Database:	USA EDM 5000 Multi Users DB
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum


Offset Design SEC 32-T7S-R20E - Three Rivers #32-34-720 - DD - Plan #1													Offset Site Error:	0.0 ft
Survey Program: 0-MWD													Offset Well Error:	0.0 ft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Total Uncertainty Axis	Separation Factor		
7,300.0	7,298.0	7,332.3	7,300.0	12.8	14.7	-8.29	783.4	-122.7	867.1	841.3	25.76	33.660		
7,400.0	7,398.0	7,432.3	7,400.0	13.0	14.9	-8.29	783.4	-122.7	867.1	841.0	26.11	33.215		
7,500.0	7,498.0	7,532.3	7,500.0	13.1	15.0	-8.29	783.4	-122.7	867.1	840.6	26.45	32.781		
7,600.0	7,598.0	7,632.3	7,600.0	13.3	15.2	-8.29	783.4	-122.7	867.1	840.3	26.80	32.358		
7,700.0	7,698.0	7,732.3	7,700.0	13.5	15.3	-8.29	783.4	-122.7	867.1	839.9	27.14	31.946		
7,800.0	7,798.0	7,832.3	7,800.0	13.6	15.5	-8.29	783.4	-122.7	867.1	839.6	27.49	31.545		
7,900.0	7,898.0	7,932.3	7,900.0	13.8	15.6	-8.29	783.4	-122.7	867.1	839.3	27.83	31.153		
8,000.0	7,998.0	8,032.3	8,000.0	14.0	15.8	-8.29	783.4	-122.7	867.1	838.9	28.18	30.770		
8,100.0	8,098.0	8,132.3	8,100.0	14.2	16.0	-8.29	783.4	-122.7	867.1	838.6	28.53	30.397		
8,200.0	8,198.0	8,232.3	8,200.0	14.3	16.1	-8.29	783.4	-122.7	867.1	838.2	28.87	30.033		
8,300.0	8,298.0	8,332.3	8,300.0	14.5	16.3	-8.29	783.4	-122.7	867.1	837.9	29.22	29.677		
8,400.0	8,398.0	8,432.3	8,400.0	14.7	16.4	-8.29	783.4	-122.7	867.1	837.5	29.56	29.329		
8,500.0	8,498.0	8,532.3	8,500.0	14.9	16.6	-8.29	783.4	-122.7	867.1	837.2	29.91	28.990		
8,600.0	8,598.0	8,632.3	8,600.0	15.0	16.7	-8.29	783.4	-122.7	867.1	836.8	30.26	28.658		
8,700.0	8,698.0	8,732.3	8,700.0	15.2	16.9	-8.29	783.4	-122.7	867.1	836.5	30.60	28.334		
8,800.0	8,798.0	8,832.3	8,800.0	15.4	17.0	-8.29	783.4	-122.7	867.1	836.1	30.95	28.016		
8,900.0	8,898.0	8,932.3	8,900.0	15.6	17.2	-8.29	783.4	-122.7	867.1	835.8	31.30	27.706		
9,000.0	8,998.0	9,032.3	9,000.0	15.7	17.4	-8.29	783.4	-122.7	867.1	835.4	31.64	27.403		
9,006.0	9,004.0	9,038.3	9,006.0	15.7	17.4	-8.29	783.4	-122.7	867.1	835.4	31.66	27.385	CC, ES, SF	

Anticollision Report

Company:	Axia Energy	Local Co-ordinate Reference:	Well Three Rivers #32-35-720
Project:	Uintah County, UT	TVD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Reference Site:	SEC 32-T7S-R20E	MD Reference:	KB=16' @ 4807.0ft (Original Well Elev)
Site Error:	0.0ft	North Reference:	True
Reference Well:	Three Rivers #32-35-720	Survey Calculation Method:	Minimum Curvature
Well Error:	0.0ft	Output errors are at	2.00 sigma
Reference Wellbore	DD	Database:	USA EDM 5000 Multi Users DB
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to KB=16' @ 4807.0ft (Original Well Elev)
Offset Depths are relative to Offset Datum
Central Meridian is -111.500000 °

Coordinates are relative to: Three Rivers #32-35-720
Coordinate System is US State Plane 1983, Utah Northern Zone
Grid Convergence at Surface is: 1.19°



AFFIDAVIT OF SURFACE USE AND GRANT OF EASEMENT

I, Tab McGinley, Affiant, being duly sworn depose and say:

THAT, I am the Vice President of Land for Axia Energy, LLC, a Delaware limited liability corporation authorized to do business in Colorado (hereinafter referred to as "Axia"), 1430 Larimer Street, Suite 400, Denver, CO 80202. Axia owns, operates and manages oil and gas interests in the State of Utah including the lands described below located in Uintah County, Utah.

WHEREAS, Axia has on file a signed Surface Use and Grant of Easement for lands located in Uintah County as follows:

TOWNSHIP 7 SOUTH, RANGE 20 EAST, SLM

Section 32: S2SW4; NE4/SW4

Containing 120 acres, more or less, Uintah County, Utah

Land Owner: Kay Anderson

THEREFORE, Axia is filing this Affidavit of Record in the records of Uintah County, Utah to ***provide constructive notice to the public*** and that any inquiries or emergencies that may occur, which require immediate notification and handling by Axia should be directed to:

AXIA ENERGY, LLC
1430 Larimer Street
Suite 400
Denver, CO 80202
Main Phone: 720-746-5200
Emergency Phone: 1-800-474-2430

Further Affiant sayeth not.

Subscribed and sworn to before me this 11th day of November, 2011.

Tab McGinley
Vice President of Land

STATE OF COLORADO) } ss
COUNTY OF DENVER)

The foregoing instrument was acknowledged before me by Tab McGinley, Vice President of Land, this 11th day of November, 2011.

Cindy A. Jumeo
Notary Public

Notary Seal:

Cindy J. Turner
Notary Public
State of Colorado

My Commission Expires 06/04/2013

BOP Equipment

3000psi WP




EXHIBIT "F"


AXIA ENERGY

LOCATION LAYOUT FOR
THREE RIVERS 32-35-720
SECTION 32, T7S, R20E, S.L.B.&M.
535' FSL 2180' FWL

FIGURE #1

SCALE: 1" = 60'
DATE: 04-20-12
DRAWN BY: R.L.L.

NOTE:
Flare Pit is to be
located a min. of 100'
from the Well Head.



Elev. Ungraded Ground At Loc. Stake = 4792.5'
FINISHED GRADE ELEV. AT LOC. STAKE = 4791.3'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: May 23, 2012

AXIA ENERGY



TYPICAL CROSS SECTIONS FOR

THREE RIVERS 32-35-720
SECTION 32, T7S, R20E, S.L.B.&M.
535' FSL 2180' FWL


FIGURE #2

X-Section
Scale
1" = 100'


DATE: 04-20-12
DRAWN BY: R.L.L.




STA. 3+50



STA. 1+70



STA. 0+70



STA. 0+00

NOTE:

Topsoil should not be
Stripped Below Finished
Grade on Substructure Area.

APPROXIMATE ACREAGES

WELL SITE DISTURBANCE = ± 3.435 ACRES
ACCESS ROAD DISTURBANCE = ± 0.088 ACRES
PIPELINE DISTURBANCE = ± 0.096 ACRES
POWERLINE DISTURBANCE = ± 0.101 ACRES
TOTAL = ± 3.720 ACRES

* NOTE:
FILL QUANTITY INCLUDES
5% FOR COMPACTION

APPROXIMATE YARDAGES

(6") Topsoil Stripping = 2,050 Cu. Yds.
Remaining Location = 12,330 Cu. Yds.
TOTAL CUT = 14,380 CU. YDS.
FILL = 4,940 CU. YDS.

EXCESS MATERIAL = 9,440 Cu. Yds.
Topsoil & Pit Backfill = 4,900 Cu. Yds.
(1/2 Pit Vol.)
EXCESS UNBALANCE = 4,540 Cu. Yds.
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: May 23, 2012

AXIA ENERGY

TYPICAL RIG LAYOUT FOR
THREE RIVERS 32-35-720
SECTION 32, T7S, R20E, S.L.B.&M.
535' FSL 2180' FWL

FIGURE #3


SCALE: 1" = 60'


DATE: 04-20-12

DRAWN BY: R.L.L.



NOTE:
Flare Pit is to be
located a min. of 100'
from the Well Head.







API Number: 4304752737
Well Name: THREE RIVERS 32-35-720
Township T0.7 . Range R2.0 . Section 32
Meridian: SLBM
Operator: AXIA ENERGY LLC

Map Prepared:
 Map Produced by Diana Mason

Units	Wells Query
STATUS	Status
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERM	PGW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
	TA - Temp. Abandoned
	TW - Test Well
	WDW - Water Disposal
	WW - Water Injection Well
	WSW - Water Supply Well
Fields	
STATUS	
ABANDONED	
ACTIVE	
COMBINED	
INACTIVE	
STORAGE	
TERMINATED	



Well Name	AXIA ENERGY LLC THREE RIVERS 32-35-720 43047527370000			
String	SURF	PROD		
Casing Size(")	8.625	5.500		
Setting Depth (TVD)	1100	9004		
Previous Shoe Setting Depth (TVD)	0	1100		
Max Mud Weight (ppg)	8.7	9.2		
BOPE Proposed (psi)	1000	3000		
Casing Internal Yield (psi)	3930	7740		
Operators Max Anticipated Pressure (psi)	3899	8.3		

Calculations	SURF String	8.625	"
Max BHP (psi)	.052*Setting Depth*MW=	498	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	366	YES <input type="checkbox"/> diverter with rotating head
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	256	YES <input type="checkbox"/> OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	256	NO <input type="checkbox"/> OK
Required Casing/BOPE Test Pressure=		1100	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	PROD String	5.500	"
Max BHP (psi)	.052*Setting Depth*MW=	4308	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	3228	NO <input type="checkbox"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2327	YES <input type="checkbox"/> OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2569	NO <input type="checkbox"/> REasonable
Required Casing/BOPE Test Pressure=		3000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		1100	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO <input type="checkbox"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO <input type="checkbox"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO <input type="checkbox"/>
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO <input type="checkbox"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO <input type="checkbox"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO <input type="checkbox"/>
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

43047527370000 Three Rivers 32-35-720

Casing Schematic



CONFIDENTIAL

Well name:	43047527370000 Three Rivers 32-35-720	
Operator:	Axia Energy LLC	Project ID:
String type:	Surface	43-047-52737
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.700 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 89 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 115 ft

Burst

Max anticipated surface pressure: 968 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,100 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 958 ft

Directional well information:

Kick-off point 1000 ft
Departure at shoe: 2 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 2 °

Re subsequent strings:

Next setting depth: 9,004 ft
Next mud weight: 9.200 ppg
Next setting BHP: 4,303 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,100 ft
Injection pressure: 1,100 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1100	8.625	32.00	J-55	LT&C	1100	1100	7.875	8864
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	497	2480	4.988	1100	3930	3.57	35.2	417	11.85 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: August 9, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1100 ft, a mud weight of 8.7 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Well name:	43047527370000 Three Rivers 32-35-720	
Operator:	Axia Energy LLC	Project ID:
String type:	Production	43-047-52737
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 9.200 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 200 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 3,928 ft

Burst

Max anticipated surface pressure: 2,322 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 4,303 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 7,750 ft

Directional Info - Build & Drop

Kick-off point 1000 ft
Departure at shoe: 75 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 0 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9006	5.5	17.00	N-80	LT&C	9004	9006	4.767	50761

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4303	6290	1.462	4303	7740	1.80	153.1	348	2.27 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: August 9, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9004 ft, a mud weight of 9.2 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.



2580 Creekview Road
Moab, Utah 84532
435/719-2018

August 21, 2012

Mrs. Diana Mason
State of Utah
Division of Oil Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Request for Exception to Spacing – Axia Energy, LLC – **Three Rivers Federal 32-35-720**
Surface Location: 535' FSL & 2180' FWL, SE/4 SW/4, Section 32, T7S, R20E,
Target Location: 460' FSL & 2180' FWL, SE/4 SW/4, Section 32, T7S, R20E,
SLB&M, Uintah County, Utah

Dear Diana:

Axia Energy, LLC respectfully submits this request for exception to spacing (R649-3-11) based on geology since the well is located less than 460 feet to the drilling unit boundary. Axia Energy, LLC is the only owner and operator within 460 feet of the surface and target location as well as all points along the intended well bore path and are not within 460 feet of any uncommitted tracts or a unit boundary.

Thank you very much for your timely consideration of this application. Please feel free to contact Jess A. Peonio of Axia Energy, LLC at 720-746-5212 or myself should you have any questions or need additional information.

Sincerely,

Don Hamilton
Agent for Axia Energy, LLC

cc: Jess A. Peonio, Axia Energy, LLC

RECEIVED: August 21, 2012

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator AXIA ENERGY LLC
Well Name THREE RIVERS 32-35-720
API Number 43047527370000 **APD No** 6046 **Field/Unit** WILDCAT
Location: 1/4,1/4 SESW **Sec** 32 **Tw** 7.0S **Rng** 20.0E 535 FSL 2180 FWL
GPS Coord (UTM) 611185 4446354 **Surface Owner** Kay Anderson

Participants

Shane Wentzel (Axia), Brandon Bowthorpe (UELS), John Busch (dirt contractor), Don Hamilton (permit contractor)

Regional/Local Setting & Topography

This proposed well site is approximately 1.25 miles south of Pelican Lake, but the land here slopes south away from the lake and toward the Green River.

Surface Use Plan

Current Surface Use

Grazing

New Road

Miles

0.03

Well Pad

Width 260 **Length** 350

Src Const Material

Onsite

Surface Formation

UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

Four wing salt brush, some grasses

Soil Type and Characteristics

Sandy loam soil with scattered gravel on surface

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required? N

Berm Required? N

Erosion Sedimentation Control Required? N

Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N

Reserve Pit

Site-Specific Factors

Site Ranking

Distance to Groundwater (feet)
Distance to Surface Water (feet)
Dist. Nearest Municipal Well (ft)
Distance to Other Wells (feet)
Native Soil Type
Fluid Type
Drill Cuttings
Annual Precipitation (inches)
Affected Populations
Presence Nearby Utility Conduits

Final Score

Sensitivity Level

Characteristics / Requirements

Reserve pit should be 195ft by 100ft by 10ft deep. Axia plans to use a 16 mil liner and felt subliner. This appears to be adequate for this site.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? N

Other Observations / Comments

Richard Powell
Evaluator

7/18/2012
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
6046	43047527370000	LOCKED	OW	P	No
Operator	AXIA ENERGY LLC		Surface Owner-APD	Kay Anderson	
Well Name	THREE RIVERS 32-35-720		Unit		
Field	WILDCAT		Type of Work	DRILL	
Location	SESW 32 7S 20E S 535 FSL 2180 FWL GPS Coord (UTM) 611194E 4446354N				

Geologic Statement of Basis

Axia proposes to set 925 feet of surface pipe, cemented to surface. The depth to the base of the moderately saline water at this location is estimated to be at approximately 1,100 feet. A search of Division of Water Rights records shows 2 water wells within a 10,000 foot radius of the center of Section 32. Both wells are over a mile from the proposed location. Well uses are listed for irrigation, domestic, and stock watering. Depth is listed for only 1 well at 150 feet. Listed wells probably produce from the Uinta Formation. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Surface casing should be extended to cover the base of the moderately saline groundwater or the production casing cement should be brought up to or above the base of the moderately saline ground water in order to isolate it from fresher water uphole.

Brad Hill
APD Evaluator

7/31/2012
Date / Time

Surface Statement of Basis

This proposed well is on fee surface. Surface owner Kay Anderson was contacted and invited to the presite but chose not to attend. Mr. Anderson stated that he was satisfied with the placement of the well and made no requests. Shane Wentzel of Axia stated that a 16 mil liner and felt subliner would be used and this appears to be adequate for the site. Mr. Wentzel also stated that covert green paint color would be used for all tanks and equipment. This appears to be a good site for placement of this well.

Richard Powell
Onsite Evaluator

7/18/2012
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 5/23/2012

API NO. ASSIGNED: 43047527370000

WELL NAME: THREE RIVERS 32-35-720

OPERATOR: AXIA ENERGY LLC (N3765)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: SESW 32 070S 200E

Permit Tech Review: ☒

SURFACE: 0535 FSL 2180 FWL

Engineering Review: ☒

BOTTOM: 0460 FSL 2180 FWL

Geology Review: ☒

COUNTY: Uintah

LATITUDE: 40.16019

LONGITUDE: -109.69431

UTM SURF EASTINGS: 611194.00

NORTHINGS: 4446354.00

FIELD NAME: WILDCAT

LEASE TYPE: 4 - Fee

LEASE NUMBER: FEE

PROPOSED PRODUCING FORMATION(S): WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE - LPM9046682☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 49-2262 - RNI at Green River☐ RDCC Review:☒ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: R649-3-11

Effective Date:

Siting:

☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhill
12 - Cement Volume (3) - hmacdonald
15 - Directional - dmason
23 - Spacing - dmason
25 - Surface Casing - hmacdonald

RECEIVED: August 27, 2012



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: THREE RIVERS 32-35-720

API Well Number: 43047527370000

Lease Number: FEE

Surface Owner: FEE (PRIVATE)

Approval Date: 8/27/2012

Issued to:

AXIA ENERGY LLC, 1430 Larimer Ste 400, Denver, CO 80202

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-11. The expected producing formation or pool is the WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 5 1/2 production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 2700' MD as indicated in the submitted drilling plan.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days

- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527370000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 8/28/2012	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU Pete Martin, Spud well 08/28/12 @ 08:00 hrs. Drilled to 100' and set 16" conductor casing, cement to surface, Release Pete Martin CURRENT STATUS: Wait on Pro Petro Rig - drill and set surface casing.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 07, 2012		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A	DATE 9/6/2012	

Carol Daniels - RE: Axia Energy - Section 32 Permits - Notice of Spud

From: Cordell Wold <cwold@axiaenergy.com>
To: Cordell Wold <cwold@axiaenergy.com>, Cindy Turner <cturner@axiaenergy.co...
Date: 9/6/2012 8:56 AM
Subject: RE: Axia Energy - Section 32 Permits - Notice of Spud
CC: "caroldaniels@utah.gov" <caroldaniels@utah.gov>, "davidhackford@utah.gov..."

32-35-720; Will be cementing surface casing this afternoon

*TOTAL R20F S 32 -
THREE RIVERS 32-15-720*

32-15-720; will move Pro-Petro this afternoon and be setting surface casing tomorrow afternoon
(09/07/2012)

Thanks,
Cordell Wold
701-570-5540

From: Cordell Wold
Sent: Wednesday, September 05, 2012 7:14 AM
To: Cindy Turner; richardpowell@utah.gov
Cc: caroldaniels@utah.gov; 'davidhackford@utah.gov'
Subject: Axia Energy - Section 32 Permits - Notice of Spud

32-35-720 – will be moving in Pro-Petro and setting surface casing tomorrow (09/06/2012)

32-15-720 – will be setting conductor today

Thanks,
Cordell Wold
701-570-5540

RECEIVED

SEP 06 2012

DIV. OF OIL, GAS & MINING

From: Cindy Turner
Sent: Tuesday, August 28, 2012 3:47 PM
To: richardpowell@utah.gov
Cc: Cordell Wold; caroldaniels@utah.gov
Subject: Axia Energy - Section 32 Permits - Notice of Spud

Richard, the following wells are not set-up to report Notice of Intent to Spud. I sent you an email earlier this week regarding the setting of conductor on the Three Rivers 32-35-720. Following is an update.

32-35-720 – Spud 08-28-12 - setting conductor currently – need to call in a spud notice, but don't have API #

43047527370000

32-15-720 – will be setting conductor next – need to call in a spud notice, but don't have API #

43047527360000

I will get notices submitted in the Utah DOGM website as soon as they are available.

Thanks

Cindy Turner
AXIA ENERGY, LLC
1430 Larimer Street
Suite 400
Denver, CO 80202
Phone: 720-746-5209
Cell: 303-328-8613
cturner@axiaenergy.com

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527370000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/20/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> CHANGE PROD CASING FROM 5-1/2" 17.00# N-80 LTC TO 5-1/2" 17.00# J-55 LTC </div> <div style="width: 35%; text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining Date: September 24, 2012 By: <u><i>Derek Dunt</i></u> </div> </div>		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A	DATE 9/18/2012	

Well name:	43047527330000 Three Rivers 36-23-720rev	
Operator:	Axia Energy LLC	
String type:	Surface	Project ID: 43-047-52733
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.700 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 87 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 231 ft

Burst

Max anticipated surface pressure: 814 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 925 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 804 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 9,011 ft
Next mud weight: 9.200 ppg
Next setting BHP: 4,307 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 925 ft
Injection pressure: 925 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	925	8.625	24.00	J-55	ST&C	925	925	7.972	4762
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	418	1370	3.277 ✓	925	2950	3.19 ✓	22.2	244	10.99 J ✓

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: September 24, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 925 ft, a mud weight of 8.7 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43047527370000 Three Rivers 32-35-720 rev.	
Operator:	Axia Energy LLC	Project ID:
String type:	Production	43-047-52737
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 9.200 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 200 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 3,928 ft

Burst

Max anticipated surface pressure: 2,322 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 4,303 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Directional well information:

Kick-off point 1000 ft
Departure at shoe: 75 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 0 °

Tension is based on buoyed weight.

Neutral point: 7,750 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9006	5.5	17.00	J-55	LT&C	9004	9006	4.767	34891
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4303	4910	1.141 ✓	4303	5320	1.24 ✓	131.7	247	1.88 J ✓

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: September 24, 2012
Salt Lake City, Utah


Remarks:

Collapse is based on a vertical depth of 9004 ft, a mud weight of 9.2 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527370000			
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT			
COUNTY: UINTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/15/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> CHANGE SURFACE CASING FROM 8-5/8" 32.00# J-55 STC TO 8-5/8" 24.00# J-55 STC </div> <div style="width: 35%; text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining Date: <u>September 25, 2012</u> By: <u></u> </div> </div>					
NAME (PLEASE PRINT) Cindy Turner		PHONE NUMBER 720 746-5209			
SIGNATURE N/A		TITLE Project Manager			
DATE 9/18/2012					

Well name:	43047527370000 Three Rivers 32-35-720rev	
Operator:	Axia Energy LLC	
String type:	Surface	Project ID: 43-047-52737
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.700 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 89 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 115 ft

Burst

Max anticipated surface pressure: 968 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,100 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 956 ft

Directional well information:

Kick-off point 1000 ft
Departure at shoe: 2 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 2 °

Re subsequent strings:

Next setting depth: 9,004 ft
Next mud weight: 9.200 ppg
Next setting BHP: 4,303 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,100 ft
Injection pressure: 1,100 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1100	8.625	24.00	J-55	ST&C	1100	1100	7.972	5662
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	497	1343	2.701 ✓	1100	2950	2.68 ✓	26.4	244	9.24 J ✓

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: September 24, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1100 ft, a mud weight of 8.7 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527370000			
9. FIELD and POOL or WILDCAT: WILDCAT		COUNTY: UINTAH			
STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/15/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. DEPTH CHANGE: FROM 9,006' TMD/9,004' TVD TO 7,400' TMD /7,398' TVD Cement Volumes will be adjusted accordingly.					
Approved by the Utah Division of Oil, Gas and Mining Date: <u>September 25, 2012</u> By: <u><i>Derek Dunt</i></u>					
NAME (PLEASE PRINT) Cindy Turner		PHONE NUMBER 720 746-5209			
SIGNATURE N/A		TITLE Project Manager			
DATE 9/18/2012					

CONFIDENTIAL

Carol Daniels - Axia, Patterson #51 Production casing & cement *T07S R20E S-32*

From: klbascom <klbascom@ubtanet.com>
To: Carol Daniels <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, ...
Date: 9/12/2012 3:08 PM
Subject: Axia, Patterson #51 Production casing & cement

Axia Energy well Three Rivers 2-11-820, API#43-047-51936 reached 7021' td, 9/11/12 @ 12:00. Will run 5.5" production casing & cement early Thursday morning 9/13/12, rig down & move with trucks to Three Rivers 32-35-720, API# 43-047-52737, thursday & rig up Friday 9/14/12. Test BOP Friday night. Any questions, contact Kenny Bascom @ 435-828-0697.

Thank You

Kenny Bascom

RECEIVED

SEP 12 2012

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: THREE RIVERS 32-35-720	
2. NAME OF OPERATOR: AXIA ENERGY LLC	9. API NUMBER: 43047527370000	
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202	PHONE NUMBER: 720 746-5200 Ext	9. FIELD and POOL or WILDCAT: WILDCAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S	COUNTY: UINTAH	
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/3/2012	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Spud 08-28-12 - Drilled and set 100' 16" conductor casing and cemented to surface. Release spud rig. On 09-15-12 MIRU Pro-Petro - resumed drilling operations. Drilled to 1130' and set 26 jts 8-5/8" 24# J-55 STC casing @ 1101.20' KB. Cemented with 675 sxs Class "G". RD Pro-Petro Rig. On 09-16-12 MIRU Patterson Rig 51 and resumed drilled operations. Drilled to 7,320' TMD / 7,311' TVD. Set 168 jts 5-1/2" 17.00# J-55 LTC casing @ 7,291.5' KB. Cemented with 412 Sxs Class "G". Patterson Rig 51 released 09-24-12 @ 12:00 hours. CURRENT STATUS: Wait on Completion

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 October 04, 2012

NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A		DATE 10/3/2012

Carol Daniels - Axia Energy, Patterson #51, Production Casing & Cement

From: klbascom <klbascom@ubtanet.com>
To: Carol Daniels <caroldaniels@utah.gov>, Dan Jarvis <danjarvis@utah.gov>, ...
Date: 9/22/2012 8:34 PM
Subject: Axia Energy, Patterson #51, Production Casing & Cement

5-32 T09S R20E

Axia Energy well Three Rivers 32-35-720, API#43-047-52737 reached 7320' td, 9/33/12 @ 03:30. Will run 5.5" production casing & cement late Sunday nite 9/23/12, rig down & move with trucks to Three Rivers 32-15-720, API# 43-047-52736, Monday & rig up Monday 9/24/12. Test BOP Early Tuesday morning. Any questions, contact Kenny Bascom @ 435-828-0697.


Thank You

Kenny Bascom

RECEIVED

SEP 25 2012

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527370000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/22/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The APD approved a WASATCH Completion on 08-27-2012. However, we have had a change in plans and request your approval for a GREEN RIVER Completion. The top of the WASATCH is 6,904'. Our bottom perf is at 6,892'.		
Approved by the Utah Division of Oil, Gas and Mining Date: <u>October 29, 2012</u> By: <u></u>		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A		DATE 10/23/2012

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Axia Energy, LLC Operator Account Number: N 3765
Address: 1430 Larimer Street, Suite 400
city Denver,
state CO zip 80202 Phone Number: (720) 746-5209

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304752737	Three Rivers 32-35-720		SESW	32	07S	20E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	<u>new</u>	<u>187166</u>	<u>8/28/2012</u>			<u>10/31/2012</u>	
Comments: APD APPROVED AS WASATCH - SUBMITTED APP TO COMINGLE GREEN RIVER-WASATCH NEED ENTITY NUMBER FOR GR-WS <div style="text-align: right;"> CONFIDENTIAL WSTC BHL: SESW </div>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304752736	Three Rivers 32-15-720		SWSW	32	07S	20E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	<u>new</u>	<u>187167</u>	<u>9/5/2012</u>			<u>10/18/2012</u>	
Comments: APD APPRVD AS WASATCH - DID NOT DRILL INTO WASATCH, SUBMITTED SUNDRY REQUESTING APPROVAL FOR A GREEN RIVER. NEED ENTITY NUMBER FOR GRV <div style="text-align: right;"> CONFIDENTIAL WSTC BHL: SWSW </div>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304752876	Three Rivers 32-41-720		NENE	32	07S	20E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	<u>new</u>	<u>187168</u>	<u>9/12/2012</u>			<u>10/31/2012</u>	
Comments: APD APPRVD AS WASATCH - SUBMITTED APP TO COMINGLE GREEN RIVER WASATCH NEED ENTITY NUMBER FOR GR-WS <div style="text-align: right;"> CONFIDENTIAL WSTC BHL: nene </div>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Cindy Turner

Name (Please Print)

Cindy Turner

Signature

Project Manager

Title

10/2/2012

Date

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527370000
PHONE NUMBER: 720 746-5200 Ext		9. FIELD and POOL or WILDCAT: WILDCAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/13/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Completion Operations Started October 22, 2012 and Ended on October 30, 2012. Completed Formation: Green River (5,138' to 6,892') 1st Production: October 30, 2012 1st Sales: October 31, 2012		
NAME (PLEASE PRINT) Cindy Turner		PHONE NUMBER 720 746-5209
SIGNATURE N/A		TITLE Project Manager
DATE 12/13/2012		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY December 17, 2012

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527370000
9. FIELD and POOL or WILDCAT: WILDCAT		COUNTY: UINTAH
STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/1/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input checked="" type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Axia Energy requests an extended stabilized production test time interval to March, 2013 to evaluate the economics of the completed intervals for economic viability and stabilized production.		
REQUEST DENIED Utah Division of Oil, Gas and Mining Date: December 20, 2012 By: <i>Derek Duff</i>		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A	DATE 12/13/2012	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047527370000

Insufficient information provided to approve request (see R649-3-20). Board hearing may be necessary.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐
(highlight changes)

FORM 8

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE							
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME							
2. NAME OF OPERATOR: AXIA ENERGY, LLC		7. UNIT or CA AGREEMENT NAME							
3. ADDRESS OF OPERATOR: 1430 Larimer St, Ste 400 CITY Denver STATE CO ZIP 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720							
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 535' FSL & 2,180' FWL AT TOP PRODUCING INTERVAL REPORTED BELOW: 582' FSL & 2,020' FWL SESW Sec 32-7S-20E AT TOTAL DEPTH: 380' FSL 2316' FWL SESW Sec 32-7S-20E BHL by HSM DOGM		9. API NUMBER: 4304752737							
10. FIELD AND POOL, OR WILDCAT UNDESIGNATED		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 32 07S 20E S							
12. COUNTY UINTAH		13. STATE UTAH							
14. DATE SPURRED: 8/28/2012		15. DATE T.D. REACHED: 9/23/2012							
16. DATE COMPLETED: 10/30/2012		17. ELEVATIONS (DF, RKB, RT, GL): 4,790' GL / 4,807' KB							
18. TOTAL DEPTH: MD 7,320 TVD 7,311		19. PLUG BACK T.D.: MD 7,226 TVD 7,217							
20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD							
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CBL-GR, Mud Log, SD-DSN-ACTR		23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input checked="" type="checkbox"/> (Submit copy)							
24. CASING AND LINER RECORD (Report all strings set in well)									
HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
24	16		0	100		G 124	25	0 CIR	
12-1/4	8-5/8 J-55	24	0	1,100		G 675	138	0 CIR	
7-3/4	5-1/2 J-55	17	0	7,292		G 412	170	2950 CBL	
25. TUBING RECORD									
SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	
2-7/8	6,906								
26. PRODUCING INTERVALS					27. PERFORATION RECORD				
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS	
(A) Green River	3,001	6,904	2,992	6,895	5,138 6,892	.35	198	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.									
DEPTH INTERVAL		AMOUNT AND TYPE OF MATERIAL							
5,138 - 6,892		Green River Hybrid Frac - 26,238 bbls slurry, 1,035,540 gal fluid and 629,100# 20/40 Premium White							
29. ENCLOSED ATTACHMENTS:									
<input checked="" type="checkbox"/> ELECTRICAL/MECHANICAL LOGS <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION					<input type="checkbox"/> GEOLOGIC REPORT <input type="checkbox"/> CORE ANALYSIS				
					<input type="checkbox"/> DST REPORT <input type="checkbox"/> OTHER: _____				
					<input checked="" type="checkbox"/> DIRECTIONAL SURVEY				
30. WELL STATUS: Prod									

JAN 25 2013

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES:	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
10/30/2012	11/26/2012	24	→	215	50	48	Pumping
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES:	INTERVAL STATUS:
48	35	35	31.60	1,278	233	→	Open

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES:	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
			→				
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES:	INTERVAL STATUS:
						→	

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES:	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
			→				
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES:	INTERVAL STATUS:
						→	

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES:	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
			→				
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES:	INTERVAL STATUS:
						→	

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Flared

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Green River	3,001
				Garden Gulch	4,963
				Uteland Butte	6,698
				Wasatch	6,904

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Cindy TurnerTITLE Project ManagerSIGNATURE Cindy TurnerDATE 1/21/2013

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

WELLBORE DIAGRAM (after completion)



Company:	Axia Energy, LLC
Lease Name:	Three Rivers 32-35-720
Surface Location:	SESW Sec 32-T7S-R20E, 535' FSL & 2,180' FWL
Bottom Hole Location:	SESW Sec 32-T7S-R20E, 529' FSL & 2,022' FWL
County:	Uintah, UT
Date:	1/7/2013

KB 4,807'

GL 4,790'

DRILLED 22" HOLE TO 100' - SET 16" CONDUCTOR

Cemented with 124 sxs to surface 07-30-12

DRILLED 12-1/4" HOLE TO 1130'

SURF CSG - 8-5/8" 24# J-55 ST&C (26 jts) Set 09-07-12

Cement: 675 sxs Class "G" to surface

2950' TOC

As Drilled Formation

Tops (MD)

GREEN RIVER 3,001

GARDEN GULCH 4,963

Prod Tbg Set @
6,906' 11-05-12

Uteland Butte 6,698'

Wasatch 6,904'

TMD 7,320

TVD 7,311

5,138 6,892 Green River 3 spf 198 Holes

Frac - Hybrid (slickwater/gel)

26,238 bbls slurry, 1,035,540 gal fluid & 629,100# 20/40 Premium White

DRILLED 7-3/4" HOLE TO ' 7,320' TMD

PROD CSG - 5 1/2" 17# J-55 LT&C (168 jts) Set @ 7,292' 09-24-12

Cemented with 412 sxs Class "G"

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR: AXIA ENERGY, LLC		7. UNIT or CA AGREEMENT NAME
3. ADDRESS OF OPERATOR: 1430 Larimer St, Ste 400 CITY Denver STATE CO ZIP 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 535' FSL & 2,180' FWL AT TOP PRODUCING INTERVAL REPORTED BELOW: 582' FSL & 2,020' FWL SESW Sec 32-7S-20E AT TOTAL DEPTH: 529' FSL & 2,022' FWL SESW Sec 32-7S-20E		9. API NUMBER: 4304752737
10. FIELD AND POOL, OR WILDCAT UNDESIGNATED		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 32 07S 20E S
12. COUNTY UINTAH		13. STATE UTAH

14. DATE SPUDDED: 8/28/2012	15. DATE T.D. REACHED: 9/23/2012	16. DATE COMPLETED: 10/30/2012	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 4,790' GL / 4,807' KB
18. TOTAL DEPTH: MD 7,320 TVD 7,311	19. PLUG BACK T.D.: MD 7,226 TVD 7,217	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CBL-GR, Mud Log, SD-DSN-ACTR			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input checked="" type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
24	16		0	100		G 124	25	0 CIR	
12-1/4	8-5/8 J-55	24	0	1,100		G 675	138	0 CIR	
7-3/4	5-1/2 J-55	17	0	7,292		G 412	170	2950 CBL	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8	6,906							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Green River	3,001	6,904	2,992	6,895	5,138 6,892	.35	198	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
5,138 - 6,892	Green River Hybrid Frac - 26,238 bbls slurry, 1,035,540 gal fluid and 629,100# 20/40 Premium White

29. ENCLOSED ATTACHMENTS:

- | | | | |
|---|--|---------------------------------------|--|
| <input checked="" type="checkbox"/> ELECTRICAL/MECHANICAL LOGS | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT | <input checked="" type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS | <input type="checkbox"/> OTHER: _____ | |

30. WELL STATUS:

Prod



Precision Survey Report

Client	BIGHORN	MWD Operator	O.Sticca
Energy Company	AXIA ENERGY	Rig Name	Patterson 51
Well Name	Three Rivers 32-35-720	Start Date	9/15/2012
Location	Uintah County, UT	End Date	9/21/2012
API/AFE#		Proposed Direction	294.90

Survey Number	MD ft	INC °	AZM °	TVD ft	N-S ft	E-W ft	SECT ft	DLS °/100'
TIE IN	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1	1168.00	0.30	149.10	1167.99	-2.62	1.57	-2.53	0.03
2	1200.00	0.20	358.20	1199.99	-2.64	1.61	-2.57	1.51
3	1231.00	0.50	21.10	1230.99	-2.46	1.66	-2.54	1.05
4	1263.00	1.30	297.10	1262.99	-2.16	1.39	-2.17	4.20
5	1295.00	3.40	292.70	1294.96	-1.63	0.19	-0.86	6.58
6	1327.00	5.20	291.40	1326.87	-0.74	-2.04	1.54	5.63
7	1358.00	5.90	293.00	1357.73	0.40	-4.81	4.53	2.31
8	1390.00	5.80	292.90	1389.56	1.67	-7.82	7.79	0.31
9	1422.00	5.70	292.90	1421.40	2.92	-10.77	11.00	0.31
10	1454.00	5.90	295.10	1453.23	4.23	-13.72	14.23	0.93
11	1485.00	5.60	294.00	1484.08	5.52	-16.55	17.34	1.03
12	1549.00	4.90	298.60	1547.81	8.10	-21.80	23.19	1.28
13	1612.00	4.90	297.90	1610.58	10.65	-26.54	28.56	0.09
14	1676.00	4.60	299.40	1674.36	13.19	-31.19	33.85	0.51
15	1740.00	4.50	298.50	1738.16	15.65	-35.63	38.91	0.19
16	1803.00	4.50	291.30	1800.96	17.72	-40.11	43.84	0.90
17	1898.00	4.20	291.10	1895.69	20.33	-46.83	51.03	0.32
18	1995.00	4.50	293.80	1992.41	23.14	-53.62	58.38	0.37
19	2089.00	4.00	287.50	2086.15	25.62	-60.12	65.32	0.73
20	2184.00	3.50	276.60	2180.95	26.95	-66.16	71.36	0.91
21	2278.00	4.40	285.70	2274.73	28.25	-72.49	77.64	1.16
22	2374.00	4.10	285.20	2370.46	30.15	-79.34	84.66	0.31
23	2469.00	4.10	290.00	2465.22	32.20	-85.81	91.39	0.36

JAN 25 2013

24	2566.00	4.00	288.30	2561.98	34.45	-92.28	98.21	0.16
25	2660.00	3.70	268.20	2655.77	35.38	-98.43	104.18	1.46
26	2756.00	2.90	290.80	2751.61	36.15	-103.79	109.37	1.58
27	2850.00	2.90	268.40	2845.50	36.93	-108.39	113.87	1.20
28	2945.00	2.90	273.20	2940.37	36.99	-113.19	118.25	0.26
29	3040.00	1.80	278.40	3035.29	37.35	-117.07	121.91	1.18
30	3137.00	2.00	274.40	3132.24	37.70	-120.27	124.96	0.25
31	3230.00	1.60	295.30	3225.19	38.38	-123.06	127.78	0.82
32	3325.00	2.80	295.00	3320.12	39.93	-126.36	131.42	1.26
33	3421.00	3.50	305.10	3415.98	42.60	-130.88	136.65	0.93
34	3516.00	3.30	316.80	3510.81	46.26	-135.13	142.04	0.76
35	3610.00	3.30	314.30	3604.66	50.12	-138.91	147.11	0.15
36	3706.00	3.20	302.30	3700.50	53.49	-143.16	152.37	0.71
37	3801.00	1.90	325.30	3795.41	56.20	-146.29	156.36	1.72
38	3896.00	0.60	59.00	3890.39	57.75	-146.77	157.44	2.14
39	3991.00	0.60	154.90	3985.39	57.55	-146.13	156.78	0.94
40	4086.00	0.80	185.20	4080.38	56.44	-145.98	156.17	0.44
41	4181.00	0.40	282.30	4175.38	55.85	-146.36	156.27	0.99
42	4275.00	0.60	226.50	4269.37	55.59	-147.04	156.77	0.53
43	4372.00	1.70	232.30	4366.35	54.36	-148.55	157.62	1.14
44	4466.00	2.80	222.70	4460.28	51.82	-151.21	158.97	1.23
45	4561.00	1.70	230.90	4555.20	49.22	-153.87	160.29	1.20
46	4656.00	0.90	265.90	4650.18	48.28	-155.71	161.56	1.15
47	4752.00	0.90	332.10	4746.17	48.89	-156.82	162.82	1.02
48	4847.00	0.60	287.30	4841.16	49.70	-157.64	163.91	0.67
49	4942.00	0.60	253.60	4936.16	49.71	-158.59	164.78	0.37
50	5039.00	1.10	208.30	5033.15	48.74	-159.52	165.21	0.83
51	5132.00	1.20	204.40	5126.13	47.07	-160.35	165.26	0.14
52	5226.00	1.10	233.10	5220.11	45.63	-161.47	165.68	0.62
53	5322.00	1.30	209.10	5316.09	44.13	-162.74	166.19	0.56
54	5417.00	1.50	207.00	5411.06	42.08	-163.83	166.32	0.22
55	5512.00	2.50	202.60	5506.00	39.06	-165.19	166.28	1.06
56	5607.00	1.20	189.00	5600.95	36.16	-166.14	165.92	1.43
57	5702.00	1.30	177.70	5695.93	34.10	-166.25	165.16	0.28
58	5798.00	1.40	166.00	5791.90	31.88	-165.93	163.92	0.30
59	5892.00	1.60	164.30	5885.87	29.50	-165.29	162.35	0.22
60	5987.00	1.90	168.30	5980.83	26.68	-164.62	160.55	0.34

61	6083.00	1.90	174.00	6076.77	23.54	-164.13	158.78	0.20
62	6179.00	2.10	173.30	6172.72	20.21	-163.75	157.04	0.21
63	6273.00	1.40	160.20	6266.67	17.42	-163.17	155.33	0.85
64	6369.00	1.50	163.40	6362.64	15.11	-162.41	153.67	0.13
65	6464.00	1.60	160.10	6457.61	12.67	-161.60	151.92	0.14
66	6559.00	1.90	170.60	6552.56	9.87	-160.89	150.09	0.46
67	6654.00	1.90	169.00	6647.51	6.77	-160.34	148.28	0.06
68	6747.00	2.00	169.00	6740.46	3.67	-159.73	146.43	0.11
69	6843.00	1.90	167.80	6836.40	0.47	-159.08	144.48	0.11
PTB	7056.00	1.90	167.80	7049.28	-6.44	-157.58	140.22	0.00

WELLBORE DIAGRAM (after completion)



Company: Axia Energy, LLC
Lease Name: Three Rivers 32-35-720
Surface Location: SESW Sec 32-T7S-R20E, 535' FSL & 2,180' FWL
Bottom Hole Location: SESW Sec 32-T7S-R20E, 529' FSL & 2,022' FWL
County: Uintah, UT
Date: 1/7/2013

KB 4,807'

GL 4,790'

DRILLED 22" HOLE TO 100' - SET 16" CONDUCTOR
Cemented with 124 sxs to surface 07-30-12

DRILLED 12-1/4" HOLE TO 1130'
SURF CSG - 8-5/8" 24# J-55 ST&C (26 jts) Set 09-07-12
Cement: 675 sxs Class "G" to surface

2950' TOC

STAGE 6					
5138	5376	Green River	3 spf	21 Holes	
Frac - Hybrid (slickwater/gel)					
2,352 bbls slurry, 98,613 gal fluid, & 66,900# 20/40 Premium White					
STAGE 5					
5434	5726	Green River	3 spf	30 Holes	
Frac - Hybrid (slickwater/gel)					
3,343 bbls slurry, 117,083 gal fluid, & 80,900# 20/40 Premium White					
STAGE 4					
5878	6147	Green River	3 spf	39 Holes	
Frac - Hybrid (slickwater/gel)					
4,354 bbls slurry, 172,065 gal fluid, & 99,500# 20/40 Premium White					
STAGE 3					
6,184	6,373	Green River	3 spf	33 Holes	
Frac - Hybrid (slickwater/gel)					
4,334 bbls slurry, 185,882 gal fluid & 152,300# 20/40 Premium White					
STAGE 2					
6405	6559	Green River	3 spf	39 Holes	
Frac - Hybrid (slickwater/gel)					
6,849 bbls slurry, 278,998 gal fluid & 80,800# 20/40 Premium White					
STAGE 1					
6627	6892	Green River	3 spf	36 Holes	
Frac - Hybrid (slickwater/gel)					
5,006 bbls slurry, 182,899 gal fluid & 148,700# 20/40 Premium White					

198

DRILLED 7-3/4" HOLE TO ' 7,320' TMD

PROD CSG - 5 1/2" 17# J-55 LT&C (168 jts) Set @ 7,292' 09-24-12
Cemented with 412 sxs Class "G"

As Drilled Formation
Tops (MD)

GREEN RIVER 3,001

GARDEN GULCH 4,963

Prod Tbg Set @
6,906' 11-05-12

Uteland Butte 6,698'

Wasatch 6,904'

TMD 7,320
TVD 7,311

7292'

WELLBORE DIAGRAM (after completion)



Company:	Axia Energy, LLC
Lease Name:	Three Rivers 32-35-720
Surface Location:	SESW Sec 32-T7S-R20E, 535' FSL & 2,180' FWL
Bottom Hole Location:	SESW Sec 32-T7S-R20E, 529' FSL & 2,022' FWL
County:	Uintah, UT
Date:	1/7/2013

KB 4,807'

GL 4,790'

DRILLED 22" HOLE TO 100' - SET 16" CONDUCTOR
Cemented with 124 sxs to surface 07-30-12

DRILLED 12-1/4" HOLE TO 1130'
SURF CSG - 8-5/8" 24# J-55 ST&C (26 jts) Set 09-07-12
Cement: 675 sxs Class "G" to surface

2950' TOC

As Drilled Formation
Tops (MD)
GREEN RIVER 3,001
GARDEN GULCH 4,963

5,138	6,892	Green River	3 spf	198 Holes
Frac - Hybrid (slickwater/gel)				
26,238 bbls slurry, 1,035,540 gal fluid & 629,100# 20/40 Premium White				

Prod Tbg Set @
6,906' 11-05-12

Uteland Butte 6,698'

Wasatch 6,904'

DRILLED 7-3/4" HOLE TO ' 7,320' TMD
PROD CSG - 5 1/2" 17# J-55 LT&C (168 jts) Set @ 7,292' 09-24-12
Cemented with 412 sxs Class "G"

TMD 7,320
TVD 7,311

7292'



Precision Survey Report

Client	BIGHORN	MWD Operator	O.Sticca
Energy Company	AXIA ENERGY	Rig Name	Patterson 51
Well Name	Three Rivers 32-35-720	Start Date	9/15/2012
Location	Uintah County, UT	End Date	9/21/2012
API/AFE#		Proposed Direction	294.90

Survey Number	MD ft	INC °	AZM °	TVD ft	N-S ft	E-W ft	SECT ft	DLS °/100'
TIE IN	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1	1168.00	0.30	149.10	1167.99	-2.62	1.57	-2.53	0.03
2	1200.00	0.20	358.20	1199.99	-2.64	1.61	-2.57	1.51
3	1231.00	0.50	21.10	1230.99	-2.46	1.66	-2.54	1.05
4	1263.00	1.30	297.10	1262.99	-2.16	1.39	-2.17	4.20
5	1295.00	3.40	292.70	1294.96	-1.63	0.19	-0.86	6.58
6	1327.00	5.20	291.40	1326.87	-0.74	-2.04	1.54	5.63
7	1358.00	5.90	293.00	1357.73	0.40	-4.81	4.53	2.31
8	1390.00	5.80	292.90	1389.56	1.67	-7.82	7.79	0.31
9	1422.00	5.70	292.90	1421.40	2.92	-10.77	11.00	0.31
10	1454.00	5.90	295.10	1453.23	4.23	-13.72	14.23	0.93
11	1485.00	5.60	294.00	1484.08	5.52	-16.55	17.34	1.03
12	1549.00	4.90	298.60	1547.81	8.10	-21.80	23.19	1.28
13	1612.00	4.90	297.90	1610.58	10.65	-26.54	28.56	0.09
14	1676.00	4.60	299.40	1674.36	13.19	-31.19	33.85	0.51
15	1740.00	4.50	298.50	1738.16	15.65	-35.63	38.91	0.19
16	1803.00	4.50	291.30	1800.96	17.72	-40.11	43.84	0.90
17	1898.00	4.20	291.10	1895.69	20.33	-46.83	51.03	0.32
18	1995.00	4.50	293.80	1992.41	23.14	-53.62	58.38	0.37
19	2089.00	4.00	287.50	2086.15	25.62	-60.12	65.32	0.73
20	2184.00	3.50	276.60	2180.95	26.95	-66.16	71.36	0.91
21	2278.00	4.40	285.70	2274.73	28.25	-72.49	77.64	1.16
22	2374.00	4.10	285.20	2370.46	30.15	-79.34	84.66	0.31
23	2469.00	4.10	290.00	2465.22	32.20	-85.81	91.39	0.36

24	2566.00	4.00	288.30	2561.98	34.45	-92.28	98.21	0.16
25	2660.00	3.70	268.20	2655.77	35.38	-98.43	104.18	1.46
26	2756.00	2.90	290.80	2751.61	36.15	-103.79	109.37	1.58
27	2850.00	2.90	268.40	2845.50	36.93	-108.39	113.87	1.20
28	2945.00	2.90	273.20	2940.37	36.99	-113.19	118.25	0.26
29	3040.00	1.80	278.40	3035.29	37.35	-117.07	121.91	1.18
30	3137.00	2.00	274.40	3132.24	37.70	-120.27	124.96	0.25
31	3230.00	1.60	295.30	3225.19	38.38	-123.06	127.78	0.82
32	3325.00	2.80	295.00	3320.12	39.93	-126.36	131.42	1.26
33	3421.00	3.50	305.10	3415.98	42.60	-130.88	136.65	0.93
34	3516.00	3.30	316.80	3510.81	46.26	-135.13	142.04	0.76
35	3610.00	3.30	314.30	3604.66	50.12	-138.91	147.11	0.15
36	3706.00	3.20	302.30	3700.50	53.49	-143.16	152.37	0.71
37	3801.00	1.90	325.30	3795.41	56.20	-146.29	156.36	1.72
38	3896.00	0.60	59.00	3890.39	57.75	-146.77	157.44	2.14
39	3991.00	0.60	154.90	3985.39	57.55	-146.13	156.78	0.94
40	4086.00	0.80	185.20	4080.38	56.44	-145.98	156.17	0.44
41	4181.00	0.40	282.30	4175.38	55.85	-146.36	156.27	0.99
42	4275.00	0.60	226.50	4269.37	55.59	-147.04	156.77	0.53
43	4372.00	1.70	232.30	4366.35	54.36	-148.55	157.62	1.14
44	4466.00	2.80	222.70	4460.28	51.82	-151.21	158.97	1.23
45	4561.00	1.70	230.90	4555.20	49.22	-153.87	160.29	1.20
46	4656.00	0.90	265.90	4650.18	48.28	-155.71	161.56	1.15
47	4752.00	0.90	332.10	4746.17	48.89	-156.82	162.82	1.02
48	4847.00	0.60	287.30	4841.16	49.70	-157.64	163.91	0.67
49	4942.00	0.60	253.60	4936.16	49.71	-158.59	164.78	0.37
50	5039.00	1.10	208.30	5033.15	48.74	-159.52	165.21	0.83
51	5132.00	1.20	204.40	5126.13	47.07	-160.35	165.26	0.14
52	5226.00	1.10	233.10	5220.11	45.63	-161.47	165.68	0.62
53	5322.00	1.30	209.10	5316.09	44.13	-162.74	166.19	0.56
54	5417.00	1.50	207.00	5411.06	42.08	-163.83	166.32	0.22
55	5512.00	2.50	202.60	5506.00	39.06	-165.19	166.28	1.06
56	5607.00	1.20	189.00	5600.95	36.16	-166.14	165.92	1.43
57	5702.00	1.30	177.70	5695.93	34.10	-166.25	165.16	0.28
58	5798.00	1.40	166.00	5791.90	31.88	-165.93	163.92	0.30
59	5892.00	1.60	164.30	5885.87	29.50	-165.29	162.35	0.22
60	5987.00	1.90	168.30	5980.83	26.68	-164.62	160.55	0.34

61	6083.00	1.90	174.00	6076.77	23.54	-164.13	158.78	0.20
62	6179.00	2.10	173.30	6172.72	20.21	-163.75	157.04	0.21
63	6273.00	1.40	160.20	6266.67	17.42	-163.17	155.33	0.85
64	6369.00	1.50	163.40	6362.64	15.11	-162.41	153.67	0.13
65	6464.00	1.60	160.10	6457.61	12.67	-161.60	151.92	0.14
66	6559.00	1.90	170.60	6552.56	9.87	-160.89	150.09	0.46
67	6654.00	1.90	169.00	6647.51	6.77	-160.34	148.28	0.06
68	6747.00	2.00	169.00	6740.46	3.67	-159.73	146.43	0.11
69	6843.00	1.90	167.80	6836.40	0.47	-159.08	144.48	0.11
PTB	7056.00	1.90	167.80	7049.28	-6.44	-157.58	140.22	0.00



Precision Survey Report

Client	BIGHORN	MWD Operator	O.Sticca
Energy Company	AXIA ENERGY	Rig Name	Patterson 51
Well Name	Three Rivers 32-35-720	Start Date	9/15/2012
Location	Uintah County, UT	End Date	9/21/2012
API/AFE#		Proposed Direction	294.90

Survey Number	MD ft	INC °	AZM °	TVD ft	N-S ft	E-W ft	SECT ft	DLS °/100'
TIE IN	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1	1168.00	0.30	149.10	1167.99	-2.62	1.57	-2.53	0.03
2	1200.00	0.20	358.20	1199.99	-2.64	1.61	-2.57	1.51
3	1231.00	0.50	21.10	1230.99	-2.46	1.66	-2.54	1.05
4	1263.00	1.30	297.10	1262.99	-2.16	1.39	-2.17	4.20
5	1295.00	3.40	292.70	1294.96	-1.63	0.19	-0.86	6.58
6	1327.00	5.20	291.40	1326.87	-0.74	-2.04	1.54	5.63
7	1358.00	5.90	293.00	1357.73	0.40	-4.81	4.53	2.31
8	1390.00	5.80	292.90	1389.56	1.67	-7.82	7.79	0.31
9	1422.00	5.70	292.90	1421.40	2.92	-10.77	11.00	0.31
10	1454.00	5.90	295.10	1453.23	4.23	-13.72	14.23	0.93
11	1485.00	5.60	294.00	1484.08	5.52	-16.55	17.34	1.03
12	1549.00	4.90	298.60	1547.81	8.10	-21.80	23.19	1.28
13	1612.00	4.90	297.90	1610.58	10.65	-26.54	28.56	0.09
14	1676.00	4.60	299.40	1674.36	13.19	-31.19	33.85	0.51
15	1740.00	4.50	298.50	1738.16	15.65	-35.63	38.91	0.19
16	1803.00	4.50	291.30	1800.96	17.72	-40.11	43.84	0.90
17	1898.00	4.20	291.10	1895.69	20.33	-46.83	51.03	0.32
18	1995.00	4.50	293.80	1992.41	23.14	-53.62	58.38	0.37
19	2089.00	4.00	287.50	2086.15	25.62	-60.12	65.32	0.73
20	2184.00	3.50	276.60	2180.95	26.95	-66.16	71.36	0.91
21	2278.00	4.40	285.70	2274.73	28.25	-72.49	77.64	1.16
22	2374.00	4.10	285.20	2370.46	30.15	-79.34	84.66	0.31
23	2469.00	4.10	290.00	2465.22	32.20	-85.81	91.39	0.36

24	2566.00	4.00	288.30	2561.98	34.45	-92.28	98.21	0.16
25	2660.00	3.70	268.20	2655.77	35.38	-98.43	104.18	1.46
26	2756.00	2.90	290.80	2751.61	36.15	-103.79	109.37	1.58
27	2850.00	2.90	268.40	2845.50	36.93	-108.39	113.87	1.20
28	2945.00	2.90	273.20	2940.37	36.99	-113.19	118.25	0.26
29	3040.00	1.80	278.40	3035.29	37.35	-117.07	121.91	1.18
30	3137.00	2.00	274.40	3132.24	37.70	-120.27	124.96	0.25
31	3230.00	1.60	295.30	3225.19	38.38	-123.06	127.78	0.82
32	3325.00	2.80	295.00	3320.12	39.93	-126.36	131.42	1.26
33	3421.00	3.50	305.10	3415.98	42.60	-130.88	136.65	0.93
34	3516.00	3.30	316.80	3510.81	46.26	-135.13	142.04	0.76
35	3610.00	3.30	314.30	3604.66	50.12	-138.91	147.11	0.15
36	3706.00	3.20	302.30	3700.50	53.49	-143.16	152.37	0.71
37	3801.00	1.90	325.30	3795.41	56.20	-146.29	156.36	1.72
38	3896.00	0.60	59.00	3890.39	57.75	-146.77	157.44	2.14
39	3991.00	0.60	154.90	3985.39	57.55	-146.13	156.78	0.94
40	4086.00	0.80	185.20	4080.38	56.44	-145.98	156.17	0.44
41	4181.00	0.40	282.30	4175.38	55.85	-146.36	156.27	0.99
42	4275.00	0.60	226.50	4269.37	55.59	-147.04	156.77	0.53
43	4372.00	1.70	232.30	4366.35	54.36	-148.55	157.62	1.14
44	4466.00	2.80	222.70	4460.28	51.82	-151.21	158.97	1.23
45	4561.00	1.70	230.90	4555.20	49.22	-153.87	160.29	1.20
46	4656.00	0.90	265.90	4650.18	48.28	-155.71	161.56	1.15
47	4752.00	0.90	332.10	4746.17	48.89	-156.82	162.82	1.02
48	4847.00	0.60	287.30	4841.16	49.70	-157.64	163.91	0.67
49	4942.00	0.60	253.60	4936.16	49.71	-158.59	164.78	0.37
50	5039.00	1.10	208.30	5033.15	48.74	-159.52	165.21	0.83
51	5132.00	1.20	204.40	5126.13	47.07	-160.35	165.26	0.14
52	5226.00	1.10	233.10	5220.11	45.63	-161.47	165.68	0.62
53	5322.00	1.30	209.10	5316.09	44.13	-162.74	166.19	0.56
54	5417.00	1.50	207.00	5411.06	42.08	-163.83	166.32	0.22
55	5512.00	2.50	202.60	5506.00	39.06	-165.19	166.28	1.06
56	5607.00	1.20	189.00	5600.95	36.16	-166.14	165.92	1.43
57	5702.00	1.30	177.70	5695.93	34.10	-166.25	165.16	0.28
58	5798.00	1.40	166.00	5791.90	31.88	-165.93	163.92	0.30
59	5892.00	1.60	164.30	5885.87	29.50	-165.29	162.35	0.22
60	5987.00	1.90	168.30	5980.83	26.68	-164.62	160.55	0.34

61	6083.00	1.90	174.00	6076.77	23.54	-164.13	158.78	0.20
62	6179.00	2.10	173.30	6172.72	20.21	-163.75	157.04	0.21
63	6273.00	1.40	160.20	6266.67	17.42	-163.17	155.33	0.85
64	6369.00	1.50	163.40	6362.64	15.11	-162.41	153.67	0.13
65	6464.00	1.60	160.10	6457.61	12.67	-161.60	151.92	0.14
66	6559.00	1.90	170.60	6552.56	9.87	-160.89	150.09	0.46
67	6654.00	1.90	169.00	6647.51	6.77	-160.34	148.28	0.06
68	6747.00	2.00	169.00	6740.46	3.67	-159.73	146.43	0.11
69	6843.00	1.90	167.80	6836.40	0.47	-159.08	144.48	0.11
PTB	7056.00	1.90	167.80	7049.28	-6.44	-157.58	140.22	0.00

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: AXIA ENERGY LLC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Ste 400 , Denver, CO, 80202		8. WELL NAME and NUMBER: THREE RIVERS 32-35-720
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0535 FSL 2180 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 32 Township: 07.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047527370000
9. FIELD and POOL or WILDCAT: THREE RIVERS		COUNTY: UINTAH
STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/1/2013 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> NEW CENTRAL TANK FACILITY: Three Rivers CTB 32-7-20-01 See Attached for Proposal and Allocation Diagram </div> <div style="width: 35%; text-align: right;"> <p style="color: red; font-weight: bold;">Approved by the Utah Division of Oil, Gas and Mining</p> <p style="color: red; font-weight: bold;">Date: <u>October 08, 2013</u></p> <p style="color: red; font-weight: bold;">By: <u><i>D. K. Duff</i></u></p> </div> </div>		
NAME (PLEASE PRINT) Cindy Turner	PHONE NUMBER 720 746-5209	TITLE Project Manager
SIGNATURE N/A	DATE 9/11/2013	

AXIA THREE RIVERS CENTRAL TANK FACILITY

Axia Energy, LLC submits the following documentation as follow-up to verbal and email approval to commingle certain wells with common interests per attached diagram.

Allocation Proposal:

Each well that comes on will be set-up and plumbed individually with (2) 500 bbl oil tanks and (1) 500 bbl water tank for each producing well.

When production on a well basis exceeds current individual well storage, production would be gauged and an internal run ticket would be generated. The oil would then be shipped to the centralized tank facilities per attached allocation diagram.

Oil Sales from Centralized Storage Facility would be allocated back to the applicable well on a first in-first out basis and quantity would be based on the run ticket generated when the oil is sold to oil purchaser.


Proposed centralized storage facilities are set up by State or Federal lease number, or in the case of Fee wells, by common interest.

Reporting Requirements:

- When oil is transferred to the central tank battery from a well location, the volume will appear on Form 11 (Monthly Disposition Report) as transported volume for the applicable entity location.
- A Form 12 (Transfer of Oil) for the volume going to the CTB will be prepared with any applicable internal run tickets attached.

EFFECTIVE DATE: October 1, 2013

FACILITY: THREE RIVERS CTB 32-7-20-01
DESC: THREE RIVERS WELLS IN SECTION 32 OF TOWNSHIP 75-RNG 20E THAT CAN FLOW TO CENTRAL TANK BATTERY
LEASE: BASED ON COMMON INTEREST/LEASE NO FEE PRIVATE



When well tanks get full and we are unable to sell, we would move the oil to the central facility for storage/sales using an internal run ticket. Sales from the Central Tank Battery would be allocated back to the wells on a first in - first out basis.